No.	Items of work.	Quantity	Unit	Rate
	FIRST FLOOR.			Rs. a. p.
22	Burnt brick in clay superstructure ...	5,419	C.ft.	
23	Archwork brick in chunam	98		
24	Burnt stone slabs 6" thick dressed ...	387	S.ft.	
25	Plastering with chunam	110·84	S.qr.	
26	Rolled steel beams including hoisting and painting.	87	Cwt.	
27	Teak wood king post trusses 18' span complete	10	Each	
28	Teak wood work wrought and put up with oiling.	135·87	C.ft.	
29	Masonry pillars table moulded brick in mortar base and cops complete 9' x¾' x¾'.	16	Each	
30	Roofing with Mangalore tiles on teak reepers complete.	31·80	S.qr.	
31	Jack arched terracing	13·60	,,	
32	Ridge tiles set in mortar and cement ...	106	R.ft.	
33	Teak wood eaves board ornamental ...	272	,,	
34	Wood railing ornamental with masonry pedestals.	124	,,	
35	Flooring with square 1st class Mangalore tiles embeded on mortar and cement pointing.	30·79	S.qr.	
36	Cornice 12" thick	156	R.ft.	
37	Chunam borders	104		
38	Parapet wall	156		
39	Teak wood with panelled shutters 1½" complete with fitting.	109	S.ft.	
40	Teak wood windows with iron bars outside panelled shutters inside glazed shutters with fitting complete.	90	,,	
41	Teak wood fan light	21	,,	
42	Moulding over windows 6"	172	R.ft.	
43	Silicate painting	8,22	S.qr.	
44	White and colour washing	110·84	,,	
45	Finials teak wood	6	Each	

R. W. SCALDWELL,
Executive Engineer.

MEDICAL DEPARTMENT.

DISTRICT HOSPITAL, KOLAR.

Abstract Notification dated 18th December 1926.

The public are hereby informed that sealed tenders in triplicate on half sheet foolscap size paper, will be received by the District Medical Officer, Kolar, at his Office at 11 A.M., on Monday the 10th January 1927, for the supply of bedding and clothing and uniform to menials required for the use of the District Hospital, Kolar, for the year 1927, commencing from 1st January 1927 to 31st December 1927 (both days inclusive).

For further details, *vide* detailed notification dated 13th December 1926, published at pages 1054 and 1055, Part VI of the *Mysore Gazette*, dated 16th December 1926.

C. NARAYANA RAO,
District Medical Officer.

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notice dated 22nd December 1926.

Notice is hereby given that sealed tenders will be received at the office of the Chief Electrical Engineer in Mysore, Bangalore, up to 22nd January 1927, for constructing five blocks of Cooly Quarters, with two units of Latrine at Kankanhalli. The tenders will be opened in public at 2 P.M., on Monday the 24th January 1927. The time required to complete the work and monthly progress, should be indicated, as these will be some of the Chief Factors in the award of tenders.

2. The plans, detailed estimate and the conditions may be obtained at the Chief Electrical Engineer's Office, Bangalore, and the Superintendent's Office at Kankanhalli, between the hours of 11 A.M. and 5 P.M., on all working days.